

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 16W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner for sections 10-11-14-15

CORNER MONUMENT 1" pipe with 4" brass cap.

DATE MONUMENT PLACED AND WITNESSED 9-12-61

WITNESSES TO CORNER..... 7" tamarack (S14 NBT) S40°E 27½ links



9" tamarack (S10 NBT) N57°W 78 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by double proportionate measure from corners 1 mile north; 1 mile east; 1 mile south and 1 mile west. No evidence of original corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE March 13, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler