

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 16W

Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner for sections 22|23


27|26

CORNER MONUMENT 5/8" X 2 1/2" re-enforcing rod buried 6" in approximately 6"
of sand road.

DATE MONUMENT PLACED AND WITNESSED 9-19-61

WITNESSES TO CORNER..... 6" Y. Birch (NET S23) N 68°E 51 links

7" Y. Birch (NET S27) S 45°W 66 links



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by single proportioned measurement between corners 1/2 mile North and 1 mile South and average measurement to 1/4 corner to east.

(north end of compass needle attracted by rod)

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE December 29, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler