

75

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>16W</u>	<u>H13</u>
	T <u>46N</u> R <u>16W</u>	<u>F13</u>
	T <u>46N</u> R <u>16W</u>	<u>G13</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

G13 September 27, 1994

F13 September 27, 1994

I, Stephan J. Szyszkowski, in a field survey on H13 September 29, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(H13) Quarter corner common to Section 34 T46N-R16W, and Section 3, T45N-R16W. Corner re-monumented in 1953 by Dean C. DeLaMater as follows: "This corner was found by Forestry Division survey crew, while making a partial resurvey of this area. One original B.T. still in place, in poor condition. Corner was placed and witnessed June 2, 1953". DeLaMater placed a 1" pipe with 4" Brass cap at the corner and marked the following NBTs: 8" Spruce N58E 12 links, 8" Spruce S30W 15 links.

(F13) Quarter corner common to Section 33 T46N-R16W, and Section 4 T45N-R16W. Corner reestablished by single proportionate measure along township line by Billy D. Buckler, RLS in 1963. Buckler placed a 1" pipe with a 4" aluminum cap at the corner and marked the following new bearing trees: 10" Jack Pine N13E 25 links, 10" Jack Pine N66W 20 links.

(G13) Corner common to Sections 33-34 T46N-R16W, and Sections 3-4 T45N-R16W. Corner reestablished in 1953 by Dean C. DeLaMater. DeLaMater placed a 1" pipe with a 4" brass cap at the corner and marked the following new bearing trees: 10" J. Pine N56E 9 links, 8" J. Pine S21E 31 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H13) Found and accepted the 1953 monument, as described, in good condition. The witness trees had been cut during a timber sale. Left the monument in place and marked 4 new witnesses as described below.

(F13) Found Buckler's 1963 monument as described, in good condition, and at record bearing and distance from the 1963 witnesses. The J. Pine NW is dead and standing, that to the NE is in good condition with scribing plain. Marked new witnesses as described below.

(G13) Found DeLaMater's monument as described, in good condition, at record bearing and distance from the remaining 1953 witness: the Jack Pine SE, which is now 12" dia. and in good condition. Marked a new top blaze on this tree and placed a measuring nail with tag in it. The other J. Pine witness has blown down. Left the monument in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H13) Found 1" iron pipe with 4" brass Mich. Dept. of Conservation cap. Blazed, scribed, and set measuring nails with tags in the following:

6" W. Pine N03E 70.55' "1/4S NBT"
5" Maple North 24.55' "1/4S NBT"
4" W. Pine S75E 68.0' "1/4S NBT"
3" W. Pine N65W 49.55' "1/4S NBT"
Placed a 5" squared and scribed cedar post adjacent. Bearings are magnetic.

(F13) Found 1" pipe with 4" aluminum Mich. Dept. of Conservation cap. Blazed, scribed and set measuring nails with tags in the following:
5" Jack Pine N65E 15.0' "1/4S NBT"
10" Jack Pine N25E 21.0' "1/4S NBT"
10" Jack Pine N87W 54.9' "1/4S NBT"
the 1963 witness:
12" Jack Pine N13E 17.55'
Placed 5" cedar post adjacent. Placed location poster on 8" J. Pine 152' west of cor. on N-S rd. Bearings are magnetic

(G13) Found a 1" pipe with 4" brass Mich. Dept. of Conservation cap. Blazed, scribed, and placed measuring nails with tags in the following:
5" Jack Pine S50W 7.4' "S4 NBT"
8" Jack Pine N12W 30.85' "S33 NBT"
8" Jack Pine N17E 19.1' "S34 NBT"
12" Jack Pine S21E 20.65' "S3"
Set a 5" squared and scribed cedar post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkowski Date 2-9-95

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1983
REVISED MAY 14, 1989
No. REVISED 1983