

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 13W.

----- Schoolcraft ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 19, 20, 29, 30.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap. -----

WITNESSES TO CORNER 16" W. Pine Stp. S 15° E 103 links -----

26" W. Pine Stp. N 22° E 70 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Section Corner set by Double Proportionate Measure.

Corner lies 6 links north of 40.00 ch. marker from west.

No evidence of original corner.

Corner placed and witnessed November 22, 1955.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 2/14/56
REGISTERED LAND SURVEYOR