

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T46-47 NR 13W . . .

----- Schoolcraft ----- COUNTY

DESCRIPTION OF CORNER 1/4 Section Corner between Sections 35,2

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap

WITNESSES TO CORNER 18" W. Pine S 64° E 64 links
Marked 1/4 S 35/2 NBT

18" W. Pine S 21° W 93 1/2 links
Marked 1/4 S 35/2 NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established 1/4 Corner by proportionate measure East and West along Township Line.

From Section Corner - 1/2 mile East
1/4 Corner - 1 mile West

No evidence of original corner.

Corner lies in mixed hardwoods.

Corner established and witnessed October 30, 1956.

SURVEYORS SEAL

SIGNED Billy J. Buckles DATE 11/8/56
REGISTERED LAND SURVEYOR