

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 NR. 13 W.

Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 25, 26, 35, 36

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap

WITNESSES TO CORNER 50" W. Pine Stp. S 18° E 72½ links
Marked NBT

6" Aspen N 77° W 25 links
Marked S 26 NBT

6" Aspen S 89° E 17 links
Marked S 36 NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Section Corner by double proportionate measure from:

Section Corner	1 mile	South
Section Corner	1 mile	North
Section Corner	1 mile	East
Section Corner	1 mile	West

No evidence of original Corner.

Corner established and witnessed October 29, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 11/8/56
REGISTERED LAND SURVEYOR