

MICHIGAN DEPARTMENT OF CONSERVATION

INTEROFFICE COMMUNICATION

Marquette
September 30, 1959

TO: W. J. Montgomery, Ass't. State Forest Administration
FROM: Billy D. Buckler, Registered Surveyor
SUBJECT: Land Corner Record for T47N R13W

One-quarter corner between sections 18-19 was set 11/22/55 from stumps believed to be original witness trees. Believe the corner was set in the original survey at 40.00 chains from the west instead of 40.00 chains from the east as intended. This mile is short being the last tier of sections to the west boundary of township.

This is the second case we have found with 1/4 corners set so. The Bureau of Land Management advised in the first case to correct this erroneous location as the corner was not set as the original surveyor intended. I have done this on July 3, 1959. New witness trees to the first location have been defaced.

I believe both copies of corner report form should be filed along with this explanation.

Billy D. Buckler

BDB:mlr