

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 13 W.

----- Schoolcraft ----- COUNTY

DESCRIPTION OF CORNER 1/4 Section Corner between Sections 18 and 19.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap.

WITNESSES TO CORNER 7" Jack Pine S 70° W 23 links

7" Jack Pine N 70° E 5 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner from two W. Pine B.T.'s in poor condition.

This 1/4 Corner is about 2 chains east of being midway on this mile, due to an error in the original survey.

Corner found by Ken Killmar.

Corner placed and witnessed November 22, 1955.

SURVEYORS SEAL

SIGNED

Billy D. Buckles

REGISTERED LAND SURVEYOR

DATE 2/14/56