

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 13. W.

Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner common to Section 2, 3, 10, and 11

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 30" White Pine Stump (S 10 NBT) S 51° W 130 Links

24" White Pine Stump (S 11 NBT) S 42° E 105 Links

24" White Pine Stump (S 3 NBT) N 54° W 107 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. This corner was re-established from 1/4 corner 1/2 mile west; Section corner 1 mile east and 1/4 corner 1/2 mile south. No evidence of original corner. Corner lies 3/4 chains S W of road.

Corner was placed and witnessed July 10, 1959 with J. Zollner, Assistant District Forester.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2/24/60
REGISTERED LAND SURVEYOR
Billy D. Buckler