

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 13. W

Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 11, 12, 14, and 13

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 6" White Pine (S 13 NBT) S 23° E 93 Links

6" White Pine (S 14 NBT) S 16° W 83 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. This corner was replaced at site of old rotted wood post set by unknown surveyor. Found probable line tree (Pine) 4.96 chains west. Position fits well with corners 1/2 miles east and 2 miles south. Corner lies 1/2 chain south of road.

Corner was placed and witnessed July 7, 1960 with J. Zollner, Assistant District Forester.

SURVEYORS SEAL

SIGNED *Billy D. Buckler* DATE 2/24/60
REGISTERED LAND SURVEYOR
Billy D. Buckler