MICHIGAN DEPARTMENT OF CONSERVATION

FORESTRY DIVISION

LAND CORNER RECORD

T__47 NR___13 ._W

| | Tarifori Graff T. T. COOM! |
|--------------------------|--|
| DESCRIPTION OF CORNER S | ection_corner_common_to_Section_14, 15, 22, and 23 |
| DESCRIPTION OF CORNER MA | ONUMENT_1" Pipe with 4" Brass Cap |
| WITNESSES TO CORNER _26 | "White Pine Stump (NBT) S 71° E 59 Links |
| 24 | "White Pine Stub (NBT) S 40° W 34 Links |
| | |
| | |

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. This corner was replaced from one 30" White Pine (probable B. T.) bearing S 64° W 82 Links. Position checks well with corners 1/2 mile south and 1 mile west.

Corner was placed and witnessed July 15, 1959 with J. Zollner, Assistant District Forester.

SURVEYORS SEAL

SIGNED Silly E. Suckles

REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 2/24/60