

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 47-48N N.R. 13W


Schoolcraft & Alger COUNTY

DESCRIPTION OF CORNER Sec. Corner to Secs. 3-4-33-34

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10-6-70

WITNESSES TO CORNER..... 6" Hard Maple (S4 NBT) S22°W 14.1'



12" Soft Maple (S34 NBT) N2°E 10.8'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at an L.E.S. Post. This post apparently set at an older post. Found no positive evidence of original witnesses. Found several very old blazes on nearby trees, facing the corner. Post sets on west edge of the old Grand Marais road and in line with the road to south. Found lines blazed to east and west.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 10-20-70  
REGISTERED LAND SURVEYOR