

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

✓

LAND CORNER RECORD

T. 47N N. R. 13W


Schoolcraft COUNTY

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 16-17

CORNER MONUMENT 1" pipe with 4" aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9-17-70

WITNESSES TO CORNER..... 9" Jack Pine (±S NBT) S57°E 53.8'



CIRCLE CORNER REGISTERED

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at a wood post, set by unknown surveyor. Found W. Pine, down and badly deteriorated, bearing N24°W, 8 links, for a probable, original witness. This corner lies nearly on line bet. two original Sec. Cors., ½ mile to north and south.

Corner lies in line with a straight trail road to east and in the west margin of a wet swale.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 10-15-70
REGISTERED LAND SURVEYOR