

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
SCHOOLCRAFT 3 CORNERS.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 13 W.	J-13, I-13, L-13
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-28-88, 1988, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- J-13 South 1/4 Corner of Section 35. Corner placed by Billy D. Buckler on 10-30-56. DNR Monument with 18" W. Pine, S64°E, 64 lks. & 18" W. Pine, S2°W, 93 1/2 lks.
  - I-13 S.W. Sec. Cor. of Sec. 35. Corner placed by Billy D. Buckler on 10-30-56. DNR Monument with 36" W. Pine Stump, S82°W, 68 lks. & 22" W. Pine Stump, S78°E, 77 lks.
  - L-13 South 1/4 Corner of Section 36. Corner placed by Billy D. Buckler on 10-30-56. DNR Monument with 20" W. Pine Stump, N68°W, 50 lks. & 32" W. Pine Stump, S78°E, 57 lks.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- J-13 Marked new witness trees to Buckler's corner. Both W. Pine trees had been cut.
  - I-13 Marked two new witness trees to Buckler's corner.
  - L-13 Marked new witness trees to Buckler's corner. 32" W. Pine Stump has been pushed over.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- DNR Monument at all three corners.
- J-13 5" Beech, S55°E, 14.5' & 8" W. Pine, South, 77.8' & 4" Beech, West, 2.15' & 6" Beech, North, 12.1'.
  - I-13 Buckler's 36" W. Pine Stump and 22" W. Pine Stump are still in place. Marked 5" R. Pine, S75°W, 27.0' & 6" R. Pine, N43°E, 51.6'.
  - L-13 Buckler's 28" W. Pine Stump, N68°W, 33.0' Marked 5" J. Pine, N25°W, 62.9' & 5" W. Pine, N35°E, 29.1' & 5" J. Pine, S12°E, 68.0'.

SIGNED BY Gerald L. Wiggins DATE 6-30-88

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

