

93

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey

T 47N R 13W 13

T R

T R

T R

2. Property Controlling
In Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Jul 18 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3									●				
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(13) Corner common to Sections 2-3-10-11. Corner Reestablished in 1959 by Billy D. Buckler, RLS by reference to corners 1/2 mile west, 1 mile east, and 1/2 mile south. Monument placed: 1" pipe with 4" brass cap. Witnesses to corner: 30" White Pine stump S51W 130 links, 24" White Pine stump S47E 105 links, 24" White Pine stump N54W 107 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(13) Recovered Buckler's monument, as described, with cap broken, and pipe bent over at ground level. Found the monument at record distance from the remains of all three NBT stumps. The stump S47E is rotting away, but the other two are standing. Noted error in the 1959 record of the bearings to the remaining two stumps: found them at N51W and S54W, not S51W and N54W as appears in the record. Removed the 1959 monument and in its place set a 1" ID x 36" iron pipe capped with a yellow plastic cap stamped MICH DNR LS 33986. Buried the monument at the corner, which falls in the westerly rut of a N-S trail. Centerline of Co. Rd 451 is 60 ft. north. Corner monumented by T. Stark and D. Lampela, Newberry.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) Set 1" pipe with plastic cap.
30" W. Pine stump N51W 85.8' (1959 wit)
24" W. Pine stump S54W 70.62'
Blazed, scribed, and set measuring nails
in the following:
10" R. Pine S56E 55.7' "S11 NBT"
14" Maple S10W 72.2' "S10 NBT"
8" R. Pine N39E 95.2' "S2 NBT"
8" R. Pine S38W 64.9' "S2 NBT"
Placed 6" cedar post with location tag
5' west. Bearings are magnetic.



Signed by Stephan J. Szyszkoski

Date Jan. 1, 1997

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division