

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Schoolcraft

(County)

Located in:

Corner Code #

1. Public Land Survey	T 47N R 13W	C9
	T 47N R 13W	B9
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

May 21 1996

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules thereof as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9	●	●										
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

(C9) Corner common to Sections 19-20-29-30. Corner reestablished by proportionate measurement in 1955 by Billy D. Buckler, RLS. 1" pipe with 4" brass cap at corner with the following witnesses: 16" W. Pine stp. S15E 103 links, 26" W. Pine stp. N22E 70 links.  
 (B9) Quarter corner common to Sections 19-30. Corner monumented from an original 8T in 1955 by Billy D. Buckler, RLS. Corner was marked with a 1" pipe with 4" brass cap and the following: 16" Red Pine S63W 161 links, 16" Red Pine S29E 273 links.


**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(C9) Recovered the 1955 W. Pine stump witnesses. The corner monument itself was not found. Monumented the corner at record bearing and distance from the two 1955 witnesses and marked two new accessories as described below. At the position for the corner, buried a 1" 10x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. The corner falls at the north side of a road. Corner monumented by T.Stark and D.Lampela, Newberry.  
 (B9) Recovered both 1955 witness trees, in good condition. The monument had presumably been moved by an unknown individual since 1955 as it was located to the west of the proper position. Removed the 1955 monument from its erroneous position and placed it at record bearing and distance from the two 1955 witness trees. Marked 2 new witnesses as described below. Corner witnessed by T.Stark and D.Lampela, Newberry.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(C9) Set 1" pipe with 4" MDNR cap. Blazed, scribed and set measuring nails in the following:  
 8" R. Pine N48W 62.9' "S19 NBT"  
 Twin 8" R. Pine N64E 33.8' "S20 NBT"  
 Placed a location post 15' south of the corner.

(B9) Set 1" pipe with 4" brass cap. Blazed, scribed and set measuring nails in the following:  
 6" R. Pine S50E 63.55 "1/4S NBT"  
 5" W. Pine N38E 68.5' "1/4S NBT"  
 The 1955 witnesses:  
 24" R. Pine S63W 106.4' "1/4S"  
 24" R. Pine S29E 180.1' "1/4S"  
 Placed a squared and scribed cedar post adjacent. Cor. lies north of E-W trail. Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/25/96

For the Michigan Department of Natural Resources - Forest Management Division