

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 14 W. - -

----- Schoolcraft ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 26, 27, 34, 35

DESCRIPTION OF CORNER MONUMENT 1" pipe with 1/4" brass cap -----

WITNESSES TO CORNER 9" Jack Pine S 2° E 128 links -----

18" White Pine Stp. S 81° W 35 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from remains of two White Pine stps. in proper position. Traces of stake in soil.

There is an unrecorded Bearing Tree (White Pine 18") S 50° E, 35 links (marked S 35")

Corner lies 32½ links West and 24 links North of 80.03 ch. marker from East.

Corner placed and witnessed May 29, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 6/2/56
REGISTERED LAND SURVEYOR