

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T~~47-48~~ NR ~~14-15~~-W

Alger and Schoolcraft COUNTY

DESCRIPTION OF CORNER Township Corner
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap
WITNESSES TO CORNER Twin 12" W. Pipe S 35° W 21 links to notch
12" W. Pipe N 52° W 39 links to notch

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Township Corner by Double Proportionate Measure.

South 1/2 mile to good 1/4 Corner; West 1 mile to good Section Corner;
North 10.25 chs. to pond; East 6.46 chs. to stream.

No evidence of original corner.

Corner placed and witnessed August 16, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 8/17/56
REGISTERED LAND SURVEYOR