

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 14 W.

Schoolcraft

COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 27-28-33-34
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap
WITNESSES TO CORNER 7" W. Pine S 41° W 100½ links
"S 33 NBT"
15" Red Pine S 30° E 176 links
"S 34 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from one white pine stump (probable B.T.) bearing S 69½° E 82 links.

Position checks very good with corners in all four directions.

Corner placed and witnessed 7/10/57.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 7/10/57
REGISTERED LAND SURVEYOR