MICHIGAN DEPARTMENT OF CONSERVATION

FORESTRY DIVISION

LAND CORNER RECORD

T 47 NR 14 W

				Bchoolcraft	COUNTY
DESCRIPTION	OF	CORNER	1/4 corner between	Sec. 18 27-28	
DESCRIPTION	OF	CORNER	MONUMENT1" Pi	pe with 4" brass of	AP
WITTNESSES	то	CORNER	30" W. Pine stub	8 77 ⁰ ¥ 	169 links
			7" W. Birch	¥ 77° ¥	871 links
				1/4 KBT	
					

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 corner from one white pine (probable B.T.) bearing S 64° E 28 links.

We identifying marks. Checks very good for distance and is on line between two section corners.

1/4 corner placed and witnessed 7/11/57.

SURVEYORS SEAL

SIGNED Silly & Suckles DATE 7/11/57