

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 47<sup>n</sup> NR. 14. W

Schooler<sup>s</sup> COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 20, 21, 28, 29.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 48" W. Pine Stp. (S 20 NBT) N 05° W 63 1/2 Links

15" W. Pine Stp. (NBT) S 17° W 81 Links

14" W. Pine Stp. (NBT) S 72° W 28 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced from one probable B.T. a W. Pine stump bottom bearing N 47° W 21 Links. Position checks to corners in all directions. Corner lies 1.00 chains east of road.

Corner was placed and witnessed June 7, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 8/11/60  
REGISTERED LAND SURVEYOR  
Billy D. Buckler