

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 14. W

Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 16, 17, 20, 21

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 28" W. Pine Stp. (NBT) N 4° E 23 1/2 Links

30" W. Pine Stp. (S 21 NBT) S 1° E 34 1/2 Links

34" W. Pine Stp. (S 20 NBT) S 72° W 64 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced from two W. Pine B.T.'s bearing N 76° E 45 Links and S 40° W 10 Links both stumps burned but in fair condition. Corner found by Forestry Division Survey Crew while making a retracement survey of township. Place location poster 9.00 chains west on road.

Corner was placed and witnessed June 7, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 8/11/60
REGISTERED LAND SURVEYOR
Billy D. Buckler