

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 14-15 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 25-36, T47N R15W & 30-31, T47N R14W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/14/64 with Miller

WITNESSES TO CORNER..... 9" J. Pine (S31 NBT), S 54° E, 18 1/2 Lks.



7" J. Pine (S25 NBT), N 67° W, 27 Lks.

8" J. Pine (S36 NBT), S 52° W, 32 1/2 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by Double Proportioned measurement between Section Corners 1 mile to West, East, North and South. No Original Evidence.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 10/14/1964
REGISTERED LAND SURVEYOR