

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 14W


Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 13-14

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 8/16/67

WITNESSES TO CORNER..... 12" Hard Maple (1/4S NBT) N18°E 9.6'



12" Hard Maple " S63°W 29.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one Hard Maple stump, bearing S60°E 25 links; a probable B.T. Found a down maple with chopped out face, bearing S30°W 30 links. This appears to be a witness but we find no record.

Found blazes to East & West of Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 10/26/67
REGISTERED LAND SURVEYOR