

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SCHOOLCRAFT
(County)

Located In:

Corner Code :#

1. Public Land Survey	T	47N	R	14W	F-5
	T	47N	R	14W	F-6
	T	47N	R	14W	G-6
	T		R		
2. Property Controlling in Section	S	16	T	47N R 14W	9
	S		T	R	
3. Miscellaneous	S		T	R	
Property In Sec.	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	14	15	16	17	18	19	20	21	22	23	24	25	26
4	27	28	29	30	31	32	33	34	35	36	37	38	39
5	40	41	42	43	44	45	46	47	48	49	50	51	52
6	53	54	55	56	57	58	59	60	61	62	63	64	65
7	66	67	68	69	70	71	72	73	74	75	76	77	78
8	79	80	81	82	83	84	85	86	87	88	89	90	91
9	92	93	94	95	96	97	98	99	100	101	102	103	104
10	105	106	107	108	109	110	111	112	113	114	115	116	117
11	118	119	120	121	122	123	124	125	126	127	128	129	130
12	131	132	133	134	135	136	137	138	139	140	141	142	143
13	144	145	146	147	148	149	150	151	152	153	154	155	156

I, Gerald L. Wiggins, in a field survey on 8-17 & 8-24, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-5 North 1/4 Corner of Section 16. DBT'S: 10" Sugar for Corner, 13" Sugar, N46°W, .30 lks & 10" Sugar, S54°E, .11 lks.
 F-6 Center of Section 16. Not previously set.
 G-6 East 1/4 Corner of Section 16. DBT'S: 30" W. Pine, N70°W, .09 lks & 8" Sugar, S89°E, .10 lks.
 9 East 1/16 Corner of Section 16. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-5 Set corner by single proportionate measure between West edge of lake and stream to East. Distance to N.W. Section Corner measures 2638.55' record measure was 2635.37.
 F-6 Corner set at intersection of North-South and East-West 1/4 line of Section 16.
 G-6 Corner set from a large W. Pine Stump I believe to be the original bearing tree. Distance North to another large W. Pine Stump (only one in area) fits original distance to a 42" W. Pine Line Tree. Distance South to S.E. Section Corner is 2642.52'. Record distance was 2640.0'.
 9 Corner set midpoint on line between East 1/4 Corner and Center of Section 16.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
DNR MONUMENT SET AT ALL FOUR CORNERS.

- F-5 8" Maple, S42°W, 18.3' & 8" Maple, S75°E, 1.75' & 5" Maple, N53°E, 19.4' & 5" Maple, N42°W, 15.2'
 F-6 20" W. Pine, S55°W, 12.5' & 6" W. Pine, S26°E, 6.8' & 8" W. Pine, N3°W, 12.0' & 20" W. Birch, S8°W, 2.0'.
 G-6 12" R. Maple, S88°W, 12.0' & 10" Y. Birch, N30°W, 15.4' & 6" R. Maple, N39°E, 3.9' & 8" H. Maple, S80°E, 37.8'.
 9 10" S. Maple, S24°W, 17.4' & 12" R. Maple, N50°W, 30.1' & 8" R. Maple, N12°W, 32.6' & 24" R. Maple, N19°E, 7.0'.

Signed by Gerald L. Wiggins Date 4-2-90
 Surveyor's Michigan License No. 23521

