

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SCHOOLCRAFT

(County)

Located in:

Corner Code -#

- | | | |
|------------------------------------|-------------|-----|
| 1. Public Land Survey | T 47N R 14W | E-5 |
| | T 47N R 14W | E-6 |
| | T 47N R 14W | E-7 |
| | T 47N R 14W | F-7 |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Gerald L. Wiggins, in a field survey on 8-17 19 89 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-5 N.W. Section Corner of Section 16. OBT'S: 13" Y. Birch, N44°E, 39 lks. & 12" Maple, S62 1/2°W, 62 lks.
 E-6 West 1/4 Corner of Section 16. OBT'S: 13" Maple, N8°E .08 lks. & 9" Maple, S8°W, 07 lks.
 E-7 S.W. Sec. Cor. of Sec. 16. Set by Billy D. Buckler L.S. 6-7-60 NBT'S: 28" W. Pine Stp., N4°E, 15.51' & 30" W. Pine Stp., S1°E, 22.77' & 34" W. Pine Stp., S72°W, 42.24'.
 F-7 South 1/4 Cor. of Sec. 16. Set by Billy D. Buckler L.S. 6-7-60 NBT'S: 30" W. Pine Stp., N25°E, 82.5' & 50" W. Pine Stp., S12°E, 13.86.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-5 Set corner by single proportionate measure between original S.W. Section Corner and original line tree North between Sections 8 and 9 and record distance West from lake, Distance between West side of lake and East to river fit record.
 E-6 Corner set midpoint on line between N.W. Corner and S.W. Corner of Section 16.
 E-7 Rewitnessed corner as set by Billy D. Buckler L.S. his pine stumps are still in place.
 F-7 Rewitnessed corner as set by Billy D. Buckler L.S. his N25°E pine stump is pushed over.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

● **DNR MONUMENT AT ALL FOUR CORNERS.**

- E-5 14" W. Pine, N80°E, 25.2' & 7" W. Pine, S14°E, 13.2' & 7" W. Pine, S20°W, 21.1' & 7" Maple, S40°W, 32.0' & Sign Iron, S10°W, 38.95'.
 E-6 4" W. Pine, West, 4.7' & 14" W. Pine, S45°W, 49.9' & 12" Maple, S13°W, 32.2' & 8" W. Pine, East, 42.8'.
 E-7 5" R. Pine, N80°E, 25.7' & 8" W. Pine, N38°W, 55.3' & 10" W. Pine, S55°W, 33.9' & 6" W. Pine, 24.4' & Buckler's stumps still in place. S35°W
 F-7 Buckler's 50" Stump is still in place, 8" R. Pine, S75°W, 76.5' & 8" R. Pine, S47°W, 89.2' & 6" R. Pine, S22°W, 115.3'.

Signed by Gerald L. Wiggins Date 4-2-90
 Surveyor's Michigan License No. 23521

FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, J.A.C. 1971

