

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft

Located in: Corner Code #

(County)

1. Public Land Survey

T 47N R 14W B13
T 47N R 14W C13

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

C13 Jul 03 1997

B13 Aug 11 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B13) Quarter corner common to Section 31 T47N-R14W and Section 6 T46N-R14W. Corner perpetuated in 1953 by Michigan Dept. of Conservation surveyor Dean C. DeLaMater, RLS: "This corner was found by forestry Division survey crew, while making a partial resurvey of this area. One original B.T. still in place, in good condition. Corner was placed and witnessed June 24, 1953. Corner monument: 1" pipe with 4" brass cap. Witnesses to corner: 10" J. Pine S44W 27 links, 5" Spruce S66E 12 links".
(C13) Corner common to Sections 31-32 T47N-R14W and Sections 5-6 T46N-R14W. Corner restored by Michigan Dept. of Conservation surveyor Dean C. DeLaMater, RLS in 1953: "This corner was established, by double proportionate measurement, by forestry Division survey crew, while making a partial resurvey of this area. No original evidence at corner. Corner monument: 1" pipe with 4" brass cap. Witnesses to corner: 12" J. Pine N69W 22 links, 8" J. Pine S68E 20 links".


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B13) Found the 1953 monument as described, a 1" I.D. iron pipe capped with a 4" dia. MI Dept. of Conservation tablet, in good condition, and at record bearing and distance from the two 1953 NBT's, now both cut stumps with no visible markings. Left the monument in place and marked four new witnesses as described below. Measured to adjacent monumented Section corners: 2656.02' East and 2517.93' West. Corner recovered and rewitnessed by T.Stark, Newberry District Office, MDNR.
(C13) Found the 1953 monument as described, a 1" I.D. iron pipe capped with a 4" brass MI Dept. of Conservation tablet, in good condition. The 1954 bearing trees were not recovered. Distances west to quarter corner and to township corner checks well with the record and is in proper proportion. MDNR field notes do not indicate why this corner was reestablished by double proportionate measurement rather than single. Nor do they provide enough information to determine if this is a typographical error on the DeLaMater record. Accepted the monument as a careful and faithful determination of the position of the original corner. Monument recovered and rewitnessed by T.Stark, Newberry District Office, MDNR. Centerline of a trail is 41' South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B13) Found 1" pipe with 4" brass cap. Blazed, scribed, and set measuring nails in the following:
6" W. Pine N72E 52.6' 1/4S NBT
8" W. Pine S70E 31.75' 1/4S NBT
8" W. Birch S15E 58.2' 1/4S NBT
8" J. Pine S30W 46.7' 1/4S NBT
Placed a 4" squared cedar post adjacent. Bearings are magnetic. The corner lies in a clearcut 45' W. of south edge.

(C13) Found 1" pipe with 4" brass cap. Blazed, scribed, and set measuring nails in the following:
4" J. Pine S37W 65.2' S6 NBT
4" J. Pine S28W 73.7' S6 NBT
4" J. Pine S07W 64.45' S6 NBT
4" J. Pine S16E 57.6' S5 NBT
Placed a 5" squared and scribed cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 9/3/97

For the Michigan Department of Natural Resources - Forest Management Division