

84

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft

(County)

Located in:

Corner Code #

1. Public Land Survey

T 47H R 14N C10

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

May 13 1997

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:  
(C10) Quarter corner common to Sections 29-30. Original corner location perpetuated in 1953 by Dean C. DeLaMater from an original B.T. in good condition. Description of corner monument: 1" pipe with 4" brass cap. Witnesses: 24" W. Pine stump S53E 120 links, 16" R. Pine N64W 153 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C10) Recovered the 1953 monument as described, a 1" ID iron pipe capped with a 4" dia. brass MI Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1953 W. Pine stump witness, found with notch and scribing still visible. The R. Pine witness has been destroyed. The original Y. Pine BT N24E, 23 links, now a stump with no markings visible, was also recovered at record bearing and distance. Left the monument in place and marked four new accessories as described below. Corner recovered and re-witnessed by T. Stark and D. Lampela, Newberry District Office. Corner is about 45' south of a trail road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
(C10) Found 1" pipe with 4" brass cap.

Blazed, scribed, and set measuring nails in the following:

10" Red Pine South 19.75' "1/4S NBT"

7" Twin W. Pine S44W 44.65' "1/4S NBT"

8" Jack Pine N72W 46.25' "1/4S NBT"

5" Red Pine N02E 24.60' "1/4S NBT"

Placed a 5" squared and scribed post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 3/25/98

For the Michigan Department of Natural Resources - Forest Management Division