

86

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey

T 47N R 14N 09

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

May 12 1997

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	10	9	8	7	6	5	4	3	2	1			
7													
8	19	18	17	16	15	14	13	12	11	10	9	8	7
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

A. Description of original monument and accessories and/or subsequent restoration:

(09) Quarter corner common to Sections 20-29. Corner re-monumented in 1956 at location of old tamarack stake and old squared tamarack tree by F.J. Bray. Bray placed a 1" pipe with 4" brass cap and marked the following: 9' Tamarack N21E 43 links, 12' J. Pine S19E 33.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(09) Recovered the 1956 monument as described, a 1" ID iron pipe capped with a 4" dia. brass MI Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1956 accessories, both in good condition. My measurements to adjacent section corners are 2647.48' East to a probable original corner, and 2644.22' West to an original corner. This monument is 8.7' north of a line between these section corners. I accept the monument as a careful and faithful perpetuation of the position of the original corner. Left the monument in place and marked new witnesses as described below. Corner recovered and re-witnessed by T. Stark and D. Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(09) Found 1" pipe with 4" brass cap.  
Blazed, scribed, and set measuring nails  
in the following:  
12' Tamarack N31E 20.45'  
15' J. Pine S12E 22.75'  
5' W. Pine S45W 14.9'      "1/4S NBT"  
4' J. Pine N58E 12.25'      "1/4S NBT"  
Placed a 6" squared and scribed cedar  
post adjacent. Bearings are magnetic.  
A N-S trail is about 80' East.



Signed by

*Stephan J. Szyszkoski*

Date

3/25/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division