

88

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey

T 47N	R 14W	C7
T 47N	R 14W	C8
T	R	
T	R	

2. Property Controlling
in Section

S	T	R	
S	T	R	

3. Miscellaneous
Property in Sec.

S	T	R	
S	T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

May 12 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7			●										
8	19		●		20		21		22		23		24
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C7) Corner common to Sections 17-18-19-20. Corner perpetuated in the original position by F.J. Bray in 1956 from the two original W. Pine bearing trees. Remonumented with a 1" pipe with 4" brass cap. New bearing trees: 8" Red Pine N81W 35 links, 20" White Pine stub S08E 83 links. Found no subsequent record.

(C8) Quarter corner common to Sections 19-20. Corner perpetuated in the position of the original Y. Pine corner tree by Frank J. Bray in 1956. New monument: 1" pipe with 4" brass cap. Bray's witnesses are 7" W. Pine N40W 52 links, 15" R. Pine S04E 62 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C7) Recovered the 1956 monument, as described, a 1" ID iron pipe capped with a 4" dia. brass MI Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1956 accessories. The R. Pine is now 30" dia. and in good condition. The W. Pine stub is rotting. Left the monument in place and marked new bearing trees as described below. Corner recovered and witnessed by T. Stark, and D. Lampela, Newberry District Office. No surface evidence of the original 8Ts exists. The corner lies in a road intersection with roads S and W.

(C8) Recovered the 1956 monument as described, a 1" ID iron pipe capped with a 4" dia. brass MI Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1956 witnesses. The 7" W. Pine is now 14" and in good condition. the R. Pine is standing but now dead. Left the monument in place and marked new witnesses as described below. Corner recovered and witnessed by T. Stark and D. Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C7) Found 1" pipe with 4" brass cap.
Blazed, scribed, and set measuring nails
in the following:

30" R. Pine N84W 23.1' "S18 NBT"
8" R. Pine N35W 53.75' "S18 NBT"
12" W. Pine S68W 61.9' "S19 NBT"
6" Maple S23E 59.0' "S20 NBT"

Placed a 4" squared and scribed post
adjacent. Bearings are magnetic.

(C8) Found 1" pipe with 4" brass cap.
Blazed, scribed, and set measuring nails
in the following:

14" W. Pine N37W 34.65' "1/4S"
16" R. Pine N16E 13.7' "1/4S NBT"
12" R. Pine S80E 4.45' "1/4S NBT"
10" R. Pine S08E 3.05' "1/4S NBT"

Placed a 5" Squared and scribed post
adjacent. Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

3/25/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division