

89

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft

(County)

Located in:

Corner Code #

1. Public Land Survey

T 47N R 14W 08

T R

T R

T R

2. Property Controlling in Section

S 20 T 47N R 14W 11

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

08 May 12 1997

11 Feb 10 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(08) Center of Section 20. Corner not established in the original survey. Found no subsequent record.

(11-Sec. 20) Southwest 1/16 corner, Section 20. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(08) Established the corner at the intersection of straight lines connecting opposite Quarter corners 2657.88' North, 2644.97' East, 2636.14' South, and 2640.62' West. At the position for the corner, I placed a 1" IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T. Stark and O. Lampela, Newberry District Office. The corner is 100' east of a trail road.

(11-Sec. 20) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. Only the 1/16 corners to the north (1320.13') and east (1321.20') are monumented at this time. At the position for the corner, I placed a 1" IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, I found a cedar post, placed by persons unknown 25.8' South and 3.9' East. Corner placed and witnessed by T. Stark and O. Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(08) Set 1" iron pipe with 4" MDNR cap.

Blazed, scribed, and set measuring nails in the following:

12" J. Pine N39W 29.45' "CS BT"

6" J. Pine N87E 15.85' "CS BT"

8" J. Pine S63E 9.25' "CS BT"

6" J. Pine S54W 30.6' "CS BT"

Placed a 5" squared and scribed cedar post adjacent. Bearings are magnetic.

(11) Set 1" iron pipe with 4" MDNR cap.

Blazed, scribed, and set measuring nails in the following:


10" W. Pine N40W 19.6' "SW1/16 BT"

4" W. Pine N19E 5.55' "SW1/16 BT"

8" R. Pine N69E 30.1' "SW1/16 BT"

12" R. Pine S04E 57.5' "SW1/16 BT"

Placed a 5" squared and scribed cedar post adjacent. Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

3/25/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division