

90

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey

T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_

2. Property Controlling  
In Section

S 20 T 47N R 14W     12  
S 20 T 47N R 14W     8

3. Miscellaneous  
Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

May 12 1997

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
(12-Sec. 20) South 1/16 corner Section 20. Corner not established in the original survey. Found no subsequent record.  
(8-Sec. 20) West 1/16 corner, Section 20. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(12-Sec. 20) Established the corner midway and on a straight line between Center of Section 1318.07' north and Quarter corner 1318.07' south. At the position for the corner, I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, I found a 1" iron pipe, placed by persons unknown, 1.9' north and 1.6' east, which I left in position. Corner placed and witnessed by T.Stark and D.Lampela, Newberry District Office. The monument is about 170' west of a N-S trail.

(8-Sec. 20) Established the corner midway and on a straight line between Quarter corner 1320.31' West and Center of Section 1320.31' East. At the position for the corner, I placed a 1" IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, I found a 3/4" iron pipe, placed by persons unknown, 24.0' north and 55.7' east, which I left in position. Corner placed and witnessed by T.Stark and D.Lampela, Newberry District Office. The corner lies in the south edge of a trail road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) Set 1" pipe with 4" MDNR cap.  
Blazed, scribed, and set measuring nails  
in the following:

8" J. Pine N87E 42.5'     "S1/16 BT"  
6" J. Pine N40E 22.9'     "S1/16 BT"  
10" J. Pine N07E 7.75'     "S1/16 BT"  
14" J. Pine N82W 12.9'     "S1/16 BT"

Placed a 5" squared and scribed post adjacent. Bearings are magnetic.

(8) Set 1" iron pipe with 4" MDNR cap.  
Blazed, scribed, and set measuring nails  
in the following:

12" W. Pine S20E 25.1'     "W1/16 BT"  
14" R. Pine S19W 32.5'     "W1/16 BT"  
10" R. Pine N44W 38.95'     "W1/16 BT"  
14" W. Pine N21E 18.2'     "W1/16 BT"

Placed a 4" squared and scribed cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 3/25/98

For the Michigan Department of Natural Resources - Forest Management Division