

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47N N.R. 15W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Sec. cor. for secs. 25, 26, 35, 36

CORNER MONUMENT 1" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 3/21/67, F. J. Bray and W. Miller

WITNESSES TO CORNER..... 4" W. Pine (NBT) S62°E, 100 lks.



5" J. Pine (NBT) N16°W, 122 lks.

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by double proportioned measurement between section corners one mile to north, south, east, and west.

SURVEYOR'S SEAL

SIGNED *F. J. Bray*
F. J. Bray
REGISTERED LAND SURVEYOR

DATE 4/6/67