

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47N N.R. 15W


Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/4 Cor. bet. Secs. 19-30

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10-29-69

WITNESSES TO CORNER..... 11" Soft Maple (1/4 S NBT) S5°W 22.6'



10" Hemlock (1/4 S NBT) N40°E 15.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at an old wood post set by F. J. Brotherton, R.D.S. Found remains of two witness trees; a Maple bearing N25°W 19 links and a Hemlock stump bottom, bearing S64°E, 45 links.

Corner position checks with corners, 1/2 mile to East and 1/2 mile to west.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 3-24-70
REGISTERED LAND SURVEYOR