

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T..47. NR..15...W

Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 10, 11, 14, 15

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 30" W. Pine Stump (S 11 NBT) N 38° E 83 Links

30" W. Pine Stump (NBT) N 13° W 64 Links

30" W. Pine Stump (S 15 NBT) S 11° W 69 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was replaced from one W. Pine B.T. bearing N 62 1/2° E 31 Links. Tree has been cut and is laying on ground. Badly rotted and burned. Found upper blaze and some scribe marks.

Corner was placed and witnessed June 14, 1960 with Russell Hinds.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 8/11/60  
REGISTERED LAND SURVEYOR  
Billy D. Buckler