

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 15 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 14-15-22-23

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/10/64 with Miller

WITNESSES TO CORNER..... 22" W. Pine Stump, (NBT), N 77° W, 74 lks.



24" W. Pine Stump, (NBT), N 25° E, 58 lks.

24" W. Pine Stump, (NBT), S 26° W, 89½ lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by Double Proportioned measurement between 1/4 Corners 1/2 mile to South, North and West and Section Corner 1 Mile to East.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 10/14/1964
REGISTERED LAND SURVEYOR