

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 15. W. . .

----- Schoolcraft ----- COUNTY

DESCRIPTION OF CORNER 1/4 Section Corner between Sections 10 and 15 . . .

DESCRIPTION OF CORNER MONUMENT 1" pipe with 1/4" brass cap . . .

WITNESSES TO CORNER 14" White Pine Stp. . . . N. 11° E . . . 35 links . . .

16" White Pine . . . S 51° W . . . 23 1/2 links . . .

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner from two White Pine stumps in proper position, no identifying marks.

Down White Pine at corner has been squared many years ago.

Location agrees with Section Corner 1/2 mile West as set by Brotherton.

Traces of stake (possible) in soil.

Corner placed and witnessed July 31, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckles  
REGISTERED LAND SURVEYOR

DATE 8/1/56