

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47N N.R. 15W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 2-3-10-11

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 8-21-62

WITNESSES TO CORNER..... 12" W. Pine (S3 NBT) N34°W, 15 links



15" W. Pine (S11 NBT) S64°E, 33½ links

15" W. Pine (S10 NBT) S22°W, 43 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced at wood stake set by unknown surveyor. Found old blazes to south. Distance checks to swamp edge north and to waters edge east, west and south.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE march 7, 1963
REGISTERED LAND SURVEYOR
Billy D. Buckler