

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD ✓

T. ~~46-47~~ NR. 16 W.

Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 5, 6, 31, and 32.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 12" W. Pine (S 5 NBT) S 45° E 26 Links

9" Hemlock (S 6 NBT) S 78° W 36 Links

9" Soft Maple (S 32 NBT) N 2° E 08 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established by single proportionate measure along E. - W. township line. Found numerous blazes at corner but no evidence of original B.T.'s. These could have been removed during logging operations. Placed location poster 5.00 chains north on road.

Corner was placed and witnessed August 4, 1960.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 8/12/60 -

Billy D. Buckler