

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T..47. NR..16. W.

----- Schoolcraft ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 29, 30, 31, 32 . . .

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap

WITNESSES TO CORNER 12" Cedar - S 31 E - 48 Links

12" Cedar - S 71 W - 37 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. Stream crossings 3.90 ch. South and 1.10 ch. West check o.k.. One probable original B.T. still in place, badly rotted.

Corner was placed and witnessed June 29, 1954.

SURVEYORS SEAL

SIGNED *John C. Anderson* DATE 2/25/55
REGISTERED LAND SURVEYOR