

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N. R. 16W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Corner for Sections 15, 16, 21 and 22.

CORNER MONUMENT 1" x 36" Iron pipe buried 6" below surface in East wheel track.

DATE MONUMENT PLACED AND WITNESSED 5-16-63.

WITNESSES TO CORNER..... 10" Soft Maple (S. 22) (N.B.T.) S. 40⁰ E., 40 lks.



10" Soft Maple (S. 16) (N.B.T.) N. 79⁰ W., 35 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by double proportioned measurement bet.
 $\frac{1}{4}$ cors. $\frac{1}{2}$ mile to South and North and West and N.C. to East.

SURVEYOR'S SEAL

SIGNED Billy D. Buckles DATE 1/2/64
REGISTERED LAND SURVEYOR