

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 47 N.R. 16W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Sec. Cor. for Secs. 9, 10, 15 and 16.

CORNER MONUMENT 1" Iron pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 5-15-63

WITNESSES TO CORNER..... 20" W. Pine (S. 10) (N.B.T.), N. 59<sup>0</sup> E., 119 lks.



3" W. Pine (X) , S. 40<sup>0</sup> W., 63 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced at wood post. Found 12" Tamarack (N. 75<sup>0</sup> E. 117 lks.) down and rotted; inverted notch in over growth and scar tissue found of faces.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 1/2/84  
REGISTERED LAND SURVEYOR