

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N. R. 16W

Schoolcraft COUNTY


DESCRIPTION OF CORNER Section corner for Sections 7 | 8

18 | 17

CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9-21-61

WITNESSES TO CORNER..... Cedar (NBT S17) S15°E 50 links



W. Birch (NBT S8) N27°E 40½ links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by double proportioned measurement to corners 1 mile North, South and west and to $\frac{1}{4}$ corner $\frac{1}{4}$ mile east.

No original evidence.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE December 29, 1961
REGISTERED LAND SURVEYOR
Billy D. Buckler