

62

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey

T 47N R 16W K5

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Nov 14 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(K5) Corner common to Sections 11-12-13-14. Corner perpetuated and re-monumented in 1953 by Dean C. DeLaHater, RLS from an original bearing tree. Corner monument: 1" pipe with 4" brass cap. Witnesses to corner: 18" Y. Birch N67E 20 links, 10" S. Maple S41W 38 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K5) Found the 1953 monument as described, in good condition, at record bearing and distance from the 1953 witness trees, both in good condition. Left the monument in place, set measuring nails in the 1953 accessories, and marked two new trees as described below. Corner re-witnessed by T. Stark and D. Lampela, Newberry.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K5) Found 1" pipe with 4" brass Mich. Dept. of Conservation cap. Blazed, scribed, and set measuring nails in the following:

24" Y. Birch N67E 13.4' "S12 NBT"

16" Soft Maple S41W 25.45' "S14 NBT"

18" Beech S32W 21.55' "S14 NBT"

9" Hemlock S60W 6.05' "S14 NBT"

Set scribed cedar post adjacent. Put a location poster on east side of road 35'

W. of corner. Bearings are magnetic

Signed by

Stephan J. Szyszkoski
33986

Date

12-11-96

Surveyor's Michigan License No.

For the Michigan Department of Natural Resources - Forest Management Division