

**SURVEY & REMONUMENTATION**

DEC 15 1993

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

REMONUMENTATION

RECORDED

93 DEC -6 AM 10:59

REGISTER OF DEEDS

*[Signature]*  
SHIawassee COUNTY, MICH.

Register of Deeds Stamp & File Number

for corners in

Shiawassee (County)	Located In:	Corner Code #/
Public Land Survey	T 5N R 1E	L-11
	T R	
	T R	
	T R	
Property Controlling in Section	S T R	
	S T R	
Miscellaneous Property in Sec.	S T R	
	S T R	

Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-11 1/4 cor., Sec. 25 & 36, T5N-R1E

Wood post placed by J. Wampler, 1826  
N26°E 4 lks. (2.64') 6" Willow  
S07°W 15 lks. (9.9') 5" Willow

Survey by J. A. Sellek, Sept. 1978 & Dec. 1979 recorded in L. 3, pg. 103 & L. 3, pg. 292 of Surveys. Used cor. as recorded in L. 1, pg. 92 of Corners.

Survey by H. C. Main, Co. Surveyor, Oct. 1887, recorded in Book D/E pgs. 170 & 171 & C.R.-2, pg. 22  
N1 1/2°W 64.5 lks. (42.57') 6" Elm  
N53°20'W 48 lks. (31.68') 14" Elm

Survey by K. J. Shellenbarger, May 1993, recorded in L. 2, pg. 856 of Corners & L. 6, pgs. 488 & 490 of Surveys  
Fnd. 2 1/4" diam. pipe per L. 1 pg. 92 of Corners and Set 1/2" rod with cap #30101 inside pipe  
S45°E 137.2' (R) LS #12034 tag NE face Power Pole  
East 12' CL 18" CMP Culvert  
North 34.42' LS #30101 tag W. face 4" Hickory  
S40°E 33.25' LS #30101 tag SW face 4" Box Elder

Survey by F. N. White, Nov. 1972, recorded in L. 1, pg. 92 of Corners & L. 1, pgs. 375 & 376 of Surveys  
Fnd. iron verified from joining corners and lines  
South 23.30' N & T Box Elder  
S45°E 137.20' N & T Power Pole  
N35°E 21.45' Top of culvert  
S40°E 17.15' Top of culvert

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 1/4 cor., Sec. 25 & 36, T5N-R1E

Fnd. 1/2" rod w/cap #30101 inside 2 1/2" pipe per L. 1, pg. 92 & L. 2, pg. 856 of Corners, & L. 1, pgs. 375 & 376, L. 3, pgs. 103 & 292 & L. 6, pgs. 488 - 490 of Surveys, replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 1/4 cor., Sec. 25 & 36, T5N-R1E

Fnd. 1/2" rod w/cap #30101 inside 2 1/2" pipe per L. 1, pg. 92 & L. 2, pg. 856 of Corners, & L. 1, pgs. 375 & 376, L. 3, pgs. 103 & 292 & L. 6, pgs. 488 - 490 of Surveys, replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.  
North 34.40' Fnd. N & T #30101 in W. face 4" Hickory (R)  
S25°E 33.23' Fnd. N & T #30101 in SW face 4" Box Elder (R)  
N30°E 29.98' Chis. "+" top center 18" CMP  
S25°E 23.85' Chis. "+" top center 18" CMP



Signed by *[Signature]*  
Surveyor's Michigan License No. 12018

Date 20 NOV 93