

SURVEY & REMONUMENTATION

DEC 15 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
REMONUMENTATION

RECORDED
 93 DEC -6 AM 10:59

For corners in

Shiawassee (County)	Located In:	Corner Code #
1. Public Land Survey	T 5N R 1E	L-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS
Shiawassee
 SHIawassee COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman C. Caldwell, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13 S 1/4 cor., Sec. 36, T5N-R1E

Wood post placed by J. Wampler, 1826
 N88 1/2°W 200 lks. (132.00') 16" W. Oak
 S70°W 166 lks. (109.56') 16" Aspen

Survey by M. F. Fouty, Sept. 1976, recorded in L. 1, pg. 636 of Corners, Set 1/2" bar on twp. line at inter. of fence line North. Research disclosed no conflicting evidence

S88°39'30"E 73.19' 1/2" bar at N 1/4 cor. Sec. 1, T4N-R1E
 NE 35.28' N & T S. side 6" Elm
 ESE 92.50' N & T N. side 14" Walnut

Survey by K. J. Shellenbarger, June 1993, recorded in L. 6, pgs. 488 - 490 of Surveys, Fnd. 1/2" bar

South 5.8' Phys. painted CL road
 North 20.40' LS #18989 tag S. face fence post
 East 73.87' (73.92' R) 1/2" iron in mon. box, N 1/4 cor., Sec. 1, T4N-R1E
 N75°W 165.53' LS #30101 tag NE face 10" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 S 1/4 cor., Sec. 36, T5N-R1E

Found 1/2" bar per L. 1, pg. 636 of Corners & L. 6, pgs. 488 - 490 of Surveys. Replaced with standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group, placed monument box, and is accepted as the best available evidence of the position of the orig. cor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 S 1/4 cor., Sec. 36, T5N-R1E

Found 1/2" bar per L. 1, pg. 636 of Corners & L. 6, pgs. 488 - 490 of Surveys. Replaced with standard 20" Harrison marker as approved by Shiawassee County Peer Review Group, placed monument box, and is accepted as the best available evidence of the position of the orig. cor.
 East 73.87' Fnd. 1/2" iron rod in mon. box at N 1/4 cor., Sec. 1, T4N-R1E (R)
 North 20.45' Fnd. N & T #18989 in S. face 12" fence post (R)
 N75°W 165.55' Fnd. N & T #30101 in NE face 10" Maple (R)
 S60°W 91.82 Set N & T #12018 in N. face 15" Oak



Signed by Norman C. Caldwell Date 20 NOV 93
 Surveyor's Michigan License No. 12018