

**SURVEY & REMONUMENTATION**

DEC 15 1993

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

**REMONUMENTATION**

RECORDED

93 DEC -6 AM 10:59

REGISTER OF DEEDS

*[Signature]*  
SHIawassee COUNTY, MICH.

Register of Deeds Stamp & File Number

For corners in

Shiawassee (County)	Located In:	Corner Code #
Public Land Survey	T 5N R 1E	N-11
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

N-11 Sec. cor., 25 & 36, T5N-R1E and Sec. 30 & 31, T5N-R2E

Wood post placed by J. Wampler, 1826  
N39°W 47 lks. (31.02') 10" B. Oak  
S62°W 86 lks. (56.76') 12" W. Oak

Survey by H. C. Main, Oct. 1887, recorded in Book D/E pgs. 170 & 171 & C.R.-2 Field Book, pg. 22  
N72°E 48 lks. (31.68') 9" W. Oak  
N52 1/2°W 22 lks. (14.52') 12" W. Oak

Survey by J. A. Seltek, 1978 recorded in L. 2, pg. 121 of cor. & L. 3, pg. 103 of Surveys. Fnd. evid. of 2" rotted stake 12" below ground surface. Set 1/2" iron w/cap in line with 1/8 & 1/4 cors. to West and in line with fence line to North, dist. to 1/8 cor. same as 1/8 cor. to 1/4 (1328.48'), 10" S. of rotted stake  
S35°W 38.46' Nail in 6" Apple  
S20°E 43.35' Nail 5" Apple  
South 40.0' E-W fence line  
N40°W 30.3' Nail Thorntree  
North 26.9' Nail in cor. post

Survey by M. L. Vanraemdonck, 1984, recorded in L. 4, pg. 122 of Surveys Fnd. rerod  
North 33.00' Rerod & cap  
N30°W 38.50' N & W E. face Power Pole  
N88°W 44.20' N & W E. face 6" Hickory  
S60°W 36.24' N & W NE trunk 6" Thornapple

L.C.R.C. by N.C. Caldwell, 1992, recorded in L. 2, pg. 805 of Corners, Fnd. 1/2" bar & cap #24622  
North 33.00' Rerod & Cap  
N30°W 38.50' N & W E. face Power Pole  
N88°W 44.20' N & W E face 65" Hickory  
S60°W 36.24' N & W NE trunk 6" Thornapple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

N-11 Sec. cor., 25 & 36, T5N-R1E and Sec. 30 & 31, T5N-R2E

Fnd. 1/2" rerod w/cap #24622 per L. 2, pg. 121 & L. 2, pg. 805 of Corners and L. 3, pg. 103 & L. 4, pg. 122 of Surveys. Replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of

N-11 Sec. cor., 25 & 36, T5N-R1E and Sec. 30 & 31, T5N-R2E

Fnd. 1/2" rerod w/cap #24622 per L. 2, pg. 121 & L. 2, pg. 805 of Corners and L. 3, pg. 103 & L. 4, pg. 122 of Surveys. Replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.

North 32.63' Fnd. rerod w/cap (unreadable) (R)  
N30°W 38.30' Fnd. N & W E. face Power Pole (R)  
N70°W 44.38' Set N & T E. face 8" Hickory (R - tree)  
S15°W 22.63' Set N & T W. face 6" Elm



Signed by *[Signature]* Date 20 NOV 93  
Surveyor's Michigan License No. 12018