

DEC 15 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
REMONUMENTATION

RECORDED

93 DEC -6 AM 10:59

REGISTER OF DEEDS

Signature of Register of Deeds

SHIawassee COUNTY, MICH.

For corners in

Table with columns: Shiawassee (County), Located In:, Corner Code #, Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

Lot No. , Recorded Plat
Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 6-36.

Norman C. Caldwell, in a field survey on November, 19 93

to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

-12 1/4 cor., Sec. 36, T5N-R1E and Sec. 31, T5N-R2E

Wood post placed by J. Wampler, 1826
S45 1/2°W 14 lks. (9.24') 15" W. Oak
N17 1/2°W 80 lks. (52.80') 14" W. Oak

Survey by K. J. Shellenbarger, June 1993, L. 2, pg. 857 of Corners and L. 6, pgs. 488 - 490 of Surveys
Fnd. 1/2" rod w/LS #24622 cap per L. 2, of Cor. pg. 380
South 8.65' (R & M) PK Nail N. face fence post
S30°E 13.53' LS #25832 tag E. face 12" Elm
S10°W 20.93' LS #30101 tag E. face 8" Cherry
S89°57'23"W 2658.22' C 1/4 cor., Sec. 36 - 1/2" rerod w/LS cap #30101 cap in conc. mon.

Surveys by M. L. Vanraemdonck, 1984 & 1992, L. 2, pg. 380 of Corners, L. 4, pg. 119 & L. 6, pg. 178 of Surveys
Fnd. remains of 48" W. Oak. U.S.B.T.,
Set rerod w/cap #24622
N45°E 9.25' From approx. blaze location in line w/N-S fence line
S88°W 20.80' N & W multi. trk. Maple
South 8.65' PK fence post
S02°W 19.68' N & W 4" Oak
S05°E 13.53' N & W 6" Elm

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

-12 1/4 cor., Sec. 36, T5N-R1E and Sec. 31, T5N-R2E

Fnd. GLO U.S.B.T. (White Oak). Removed outside shell and found old blaze scar. Reconstructed the scene, the dist. (9.25') to Vanraemdonck record fits well. Held 1/2" rod with cap #24622 per L. 2, pg. 380 & pg 857 Corners and L. 4, pg. 119, L. 6, pgs. 178 & 488 of Surveys. Replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

-12 1/4 cor., Sec. 36, T5N-R1E and Sec. 31, T5N-R2E

Fnd. GLO U.S.B.T. (White Oak). Removed outside shell and found old blaze scar. Reconstructed the scene, the dist. (9.25') to Vanraemdonck record fits well. Held 1/2" rod with cap #24622 per L. 2, pg. 380 & pg 857 Corners and L. 4, pg. 119, L. 6, pgs. 178 & 488 of Surveys. Replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as a careful and faithful perpetuation of the position of the original corner.
S05°W 8.55' Fnd. PK in fence post (R)
S70°W 20.70' Fnd. N & T E. face Ironwood Cluster (R)
S10°W 20.90' Fnd. N & T #30101 E. face 6" Hickory (R)
S22°W 13.50' Fnd. N & T #25832 E. face 12" Elm (R)
S45°W 14.35' Set N & T #12018 W. fc 7" Oak
North 1' +/- Set REI carsonite witness post



Signed by [Signature] Date 20 NOV 93
Surveyor's Michigan License No. 12018