

**SURVEY &
REMONUMENTATION**

MAY 28 1997

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
COMMISSION
Shiawassee
(County)

Located in: _____ Corner Code # _____

RECORDED
96 NOV 18 PM 3:39
REGISTER OF DEEDS
Gaye Shultz
SHIAWASSEE COUNTY, MICH.

1. Public Land Survey T 5N R 2E K-9
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
In Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Mark L. VanRaemdonck, in a field survey on November 6, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1.) Original: Joseph Wampler, D.S., 1826.
Monument: Wood post
Accessories: Beech 16 S82°W 10 1/2
Sugar 5 N49°E 12 1/2
- 2.) Elmer F. Joslin, County Surveyor, April, 1902.
Monument: Found 1 1/4" gas pipe
Accessories: Elm 9" N30 1/2°E 54 1/4 links
W. Oak 6" S22 3/4°E 90 1/2 links
(Book F, page 20)
- 3.) John F. Quine, L.C.R.C. recorded Liber 1, page 571, 4/7/75.
Monument: Found 1 1/4" gas pipe 6" deep. Brought to surface with 3/8" x 6" iron rod
Accessories: Road name sign post NW 43.6'
Tele. cable warning sign at NE corner of tele. pole SW ? (1902 BT) -
Oak 30" S22 3/4°E 59.6' (90 1/2 links + 1/2 of 6" diameter = 59.98')
Stop sign post NE 46.2'
7/18/1964 Field Book 7, page 48

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" gas pipe as referenced in no. 2 and no. 3 above. Accepted this location as the original corner position based on the best available evidence. Excavation for Harrison Marker provided no further evidence. The gas pipe had been forged to a point on the bottom. Found no conflicting evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Removed gas pipe and installed a standard Shiawassee County Harrison Marker monument. The monument was stamped "REMON 24622" and is witnessed by the following accessories:

- N45°E 86.27' Set N&T in S. face util. pole
N60°W 43.79' E. face road sign post at base
S40°W 41.13' Top cen. tele. cable box
S20°W 40.00' Set rerod & cap in shoulder



Signed by Mark L. VanRaemdonck
Surveyor's Michigan License No. 24622

Date Nov. 12, 1996

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 16, 1971;
REVISED MAY 14, 1975
REVISED JAN., 1983

APPROVED
7/8/96 MLV
County Remonumentation
Peer Review Group

LIBER 1B **PG** 1716