

SURVEY & REMONUMENTATION

DEC 15 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
REMONUMENTATION

RECORDED

93 DEC -6 AM 10:58

For corners in

Shiawassee (County)	Located In:	Corner Code #
1. Public Land Survey	T 5N R 2E	K-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS
Shirley A. ...
 SHIAWASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell, in a field survey on _____ November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-12 1/4 cor., Sec. 35 & 36, T5N-R2E
 Wood post place by J. Wampler, 1826
 S24°W 9 lks. (5.94') 6" Ironwood
 N67°W 18 lks. (11.88') 21" Birch
 Survey by O. M. Elliot, date unknown,
 CR-38, pg. 51
 Monument not given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12 1/4 cor., Sec. 35 & 36, T5N-R2E
 Fnd. no evidence of a monument. Position established by using local collateral evidence and agrees well with old fence rows to N-S-E-W. Set a standard 20" Harrison marker as approved by Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 1/4 cor., Sec. 35 & 36, T5N-R2E
 Fnd. no evidence of a monument. Position established by using local collateral evidence and agrees well with old fence rows to N-S-E-W. Set a standard 20" Harrison marker as approved by Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.
 S20°E 12.15' Set N & T #12018 W. fc twin 6" Elm
 S85°E 28.29' Set N & T #12018 S. fc 15" Ash
 S70°W 20.71' Set N & T #12018 SE fc 12" Ash
 S25°W 30.13' Set N & T #12018 W. fc 12" Oak
 North 1' +/- Set REI carsonite post



Signed by *Norman C. Caldwell* Date 20 NOV 93

Surveyor's Michigan License No. 12018